3.2.1.2 Each terminal suite shall be packed into no more than three ruggedized, transportable, airline baggage-shippable cases. The Contractor shall include the cases and packing foam with each terminal suite. The maximum exterior dimensions (length+width+height) of the baggage shippable cases are 115 inches and the maximum allowed weight for each case is seventy (70) pounds. The Contractor shall ensure the size and weight of any one case does not exceed these maximum exterior dimensions and weight requirements.

3.2.1.3 All equipment delivered as part of the complex satellite solution shall be new equipment.

3.2.1.4 Terminal equipment shall be able to be unpacked, set up, and configured by one person within two hours. Terminals shall be auto-acquire with an automatic peak and pol function to allow full operation no more than 30 minutes after terminal set-up.

3.2.1.5 Satellite communications terminals shall be Ku-band.

3.2.1.6 The Contractor shall provide all original manufacturer equipment documentation with each terminal suite.

3.2.1.7 The Government will provide one ViaSat AltaSec KG-250 High Assurance Internet Protocol Encryptor (HAIPE) network encryption device per terminal suite for the Contractor to integrate with the terminal suite equipment. There is no need for the Contractor to integrate the device into the terminal equipment cases

3.2.1.8 The Contractor shall procure, configure, test, and deliver ten (10) remote terminal suites.

3.2.1.9 The Contractor shall develop a test plan and schedule for the procured terminals and provide it to the Government for review/approval no later than 30 days after award. All procured terminals shall undergo testing at the Contractor facility prior to shipment. The Government reserves the right to attend all tests. The Government will provide one KG-250 HAIPE device for testing purposes only. This device shall be returned to the Government and not shipped with the terminals. The input to the KG-250 is an Ethernet connection. The Contractor is only responsible for ensuring the Contractor provided equipment is interoperable with the KG-250. The Contractor shall provide completed test reports to the Government within ten (10) days of test completion. The Contractor shall not ship any equipment prior to Government review of test results.

3.2.1.10 The Contractor shall ensure that all components are interoperable and shall integrate all components into a single turnkey solution.

3.2.2 Equipment Service and Support

The Contractor presents an approach for lifecycle management (on-going maintenance and operational support services, customer care and help desk support to include electromagnetic interference (EMI)/radio frequency interference (RFI) resolution support, and training). The Contractor shall provide a maintenance service plan that describes how the Contractor will provide continued technical support for all equipment and minimize mean time between failure and mean time to repair including warranty service, spare parts, and field support. Field support is only required for Germany.

3.2.3 Managed Network Services

3.2.3.1 The Contractor shall provide baseline commercial satellite communications managed network services for 10 terminals operating simultaneously. The Contractor shall provide a private, dedicated managed network to support a committed information rate to each terminal of 768 kbps x 512 kbps. The network outroute(s) shall support a minimum committed information rate (CIR) of [illegible]

3.2.4.1 The Contractor shall describe the frequency clearance requirements and explain how the requirements will be met to allow transmission in Host Nations. The Contractor shall support Host Nation Agreement (HNA) efforts in obtaining international approvals for radio spectrum operations under this contract in foreign nations. The Contractor shall ensure that international services provided under this contract may be provided as scheduled with the full approval of each affected host nation. Typical services may include, but are not limited to: host nation approvals, landing rights, operating agreements, site licenses, and frequency clearances.

3.2.4.2 Frequency Clearances for all ten (10) terminals operating in Germany, Saudi Arabia, United Arab Emirates, Bahrain, Qatar, and Kuwait shall be required prior to the start of managed network services. Frequency clearances for all other countries within the coverage area will be requested when needed as mission dictates throughout the life of this sample task order and do not need to be priced with proposal submission.

3.2.4.3 If additional host nation support becomes necessary during the life of the Task Order, contract line item numbers will be added to the order at the time they are required and shall be invoiced at pass-through rates. The Contractor may be required to provide HNAs for any nation covered within the limits defined in the coverage area, as needed by the user.

3.2.4.4 Frequency Clearances shall be requested for the maximum time period allowed by the host nation, up to the life of the contract.

3.2.4.5 The Contractor shall provide the Government with copies of regulatory licenses and approvals obtained to operate and use the spectrum for countries within the required service region. This will be a post-award contract deliverable. See Section L.22.2 regarding submission of post-award contract deliverables.

3.2.5 Training Support